

Estimated Amount : Rs 75,969.00

<b>Name of work:-Supplying,fitting&amp; fixing of PAVER BLOCK(60mm.thick)top pavement in front of Girls Hostel building of B.B.College, Asansol. Estimated Area= (22.22x1.80)=40.00 Sqm.</b>						
Estimate prepared as per PWD Schedule with effect from 01.11.2017						
Page no	Sl.	Description of the Item	Quantity	Unit	Rate	Amounts
P-1 Item no: 2(a)	1	Earth work in excavation for foundation,trenches drains in all sorts of soil(including mixed soil but excluding laterite or sand stone)including removing spreading or stacking the soils within a lead of 75mtr as directed. The items include necessary trimming the sides of trenches levelling,dressing and ramming the bottom boiling out water as per required complete				
		a) Depth of excavation not exceeding 1500 mm.	8.00	Cum.	119.27	954.16
P-1 Item no: 3	2	Filling in foundation or plinth by silver sand in consolidating same by through saturation with water and ramming complete,including the cost of supply of sand (Payment to be made on measurement of finished quantity).				
			6.00	Cum.	543.51	3261.06
P-15 Item no: 8	3	Brick work with 1st class Brick in cement mortar(6:1)				
		b) In super structure, Ground floor.	3.85	Cum.	4998.00	19242.30
P-75 Item no:38(c)	4	Supplying & laying interlocking designer paver block of any shade and of approved quality as per IS: 1237-1980 laid in pattern as directed in pavement, footpath, driveway, etc including necessary underlay complete in all respect with all labour and material. [Border concrete if necessary to be paid separately].  (c) 60 mm thick block (over 150 mm medium sand bed including cost of sand but excluding cost of earthwork in excavation or dismantling of existing hard surface if necessary)				
		(ii) Coloured Decorative	30.00	Sqm.	1274.00	38220.00
P-24 Item no:10(a)	5	Ordinary cement concrete(mix 1:1.5:3) with graded stone chips(20 mm nominal size) excluding shuttering & reinforcement if any,in ground floor.				
		i) Pakur variety.	0.60	Cum.	5216.45	3129.87
P-189 Item no:(i)c	6	15mm th. Cement plaster to wall,floor,ceiling etc. with cement mortar (1:6)				
			22.22	Sqm.	136.00	3021.92
			Total work done value			67829.31
			Add.12% GST.			8139.51
			Total Amounts			75968.82

**Note :- Quotation Submit at Principal Chamber within  
29.03.2022 upto 12.00 Noon**